

**Project Details**

PROJECT NAME	Mt Isa Culvert
PROJECT LOCATION	Barkly Highway Mt Isa
CASA ROLE	Subcontractor
CLIENT	RoadTek
CONTRACT VALUE	\$165,000
PROJECT COMPLETION DATE	December 2011
CONSTRUCTION MANAGER	Peter Casa
PROJECT MANAGER/CONTRACT ADMINISTRATOR	Wendy Salter
SITE SUPERVISOR/SITE MANAGER	Nick Salter and Kim Dawes

**Project Scope**

Temporary strengthening work was required to an existing culvert on the Barkly Highway to maintain its structural integrity. RoadTek required a contractor who could support a prompt mobilization and complete the work prior to the pending wet season and annual leave period.

CASA established on site within 7 days of receipt of project documentation and completed the work ahead of the approved program.

CASA's scope included; removing existing bitumen and excavate to required level, install leveling pads and place concrete precast panels, supply and place high-flow-high strength concrete and assist RoadTek with placement and relocation of steel traffic barricades.

Work was carried out in two stages (one lane at a time) in order to maintain traffic flow.

